

# PLYMOUTH VALLEY ESTATES SPECIFICATIONS (Lots 1-35)

CUSTOMER'S NAME: \_\_\_\_\_

LOT/JOB NO: \_\_\_\_\_ TYPE OF HOUSE \_\_\_\_\_

1. FOUNDATION:

FOOTINGS: SIZE – 8” x 20”

FOUNDATION WALLS: 10” POURED CONCRETE

COLUMNS: 4” STEEL

GIRDERS: STEEL

EXTERIOR BASEMENT FINISH:

RUB-R-WALL WATERPROOFING ON WALLS,

EGRESS WINDOW DETERMINED BY LOT GRADING AND FIELD SUPERINTENANT

**NOTE:** MONOLITHICLY POURED CONCRETE BASEMENT WALLS WILL HAVE A TENDANCY TO DEVELOP EXPANSION AND/OR SHRINKAGE CRACKS FROM TIME TO TIME. BUILDER WILL INSTALL EXPANSION JOINTS AT THE RECOMMENDED DISTANCES. HOWEVER, CRACKS WILL STILL DEVELOP. THESE CRACKS ARE NOT STRUCTURAL AND ARE UNCONTROLLABLE. IF A CRACK SHOULD DEVELOP IT IS BEYOND THE BUILDERS CONTROL. THEREFORE, IT IS NOT THE BUILDERS' RESPONSIBILITY.

2. FIREPLACE AND CHIMNEY:

(1) FIREPLACES, 36” DIRECT VENT PRE-FAB GAS, AS PER BROCHURE PLANS.

BLACK SLATE SURROUND WITH FLUSH HEARTH SELECTION OF PAINTED WOOD MANTLES.

3. EXTERIOR WALLS:

FRONT: MANUFACTURED STONE AND SIDING PER PLAN (SEE BROCHURE)

REAR & SIDES: VINYL SIDING

SHUTTERS: AS PER FRONT ELEVATION (SEE BROCHURE)

COMPOSITE TRIM PACKAGE AS PER FRONT ELEVATION (SEE BROCHURE.) COMPOSITE TRIM ON DORMER FACE, VINYL ON THE SIDES/REAR

4. INTERIOR WALLS:

ALL INTERIOR WALLS AND CEILING: ½” DRYWALL

9’ HIGH CEILING, 1<sup>ST</sup> FLOOR

8’ HIGH CEILING, 2<sup>ND</sup> FLOOR

9’ HIGH FOUNDATION WALLS

Initial \_\_\_\_\_

Initial \_\_\_\_\_

1

## PLYMOUTH VALLEY ESTATES SPECIFICATIONS (Lots 1-35)

5. CONCRETE WORK:
  - 4" CONCRETE GARAGE FLOOR
  - 6" PAD AT FRONT DOOR
  - 4" CONCRETE WALK FROM DRIVEWAY TO FRONT DOOR
  - NOTE: CONCRETE WILL BE INSTALLED IN WORKMAN LIKE MANNER, BUT BUILDER WILL NOT BE RESPONSIBLE FOR CRACKING OR IMPERFECTIONS BEYOND HIS CONTROL.**
  
6. SUB FLOORING:
  - MATERIAL: 3/4" TONGUE AND GROOVE ADVANTECH
  - GLUED, NAILED AND SCREWED
  
7. FLOOR FRAMING:
  - JOIST MATERIAL: ENGINEERED I-JOIST OR AS REQUIRED BY TOWNSHIP CODE.
  
8. FINISHED FLOORING:
  - CARPET:** LIVING, FAMILY ROOM, STUDY, 2<sup>ND</sup> FLOOR HALL, BEDROOMS, AND CLOSETS. MAIN STAIR RUNNER TO MATCH 2<sup>ND</sup> FLOOR HALL CARPET
  - HARDWOOD: (3" ENGINEERED MULLICAN NEWTOWN PLANK)** KITCHEN, BREAKFAST AREA, SUN ROOM OR MORNING ROOM (IF APPLICABLE), POWDER ROOM AND FOYER, FIRST FLOOR HALL AND DINING ROOM
  
9. PARTITION FRAMING: (SPACED 16" ON CENTER)
  - STUDS: (MATERIAL): WOOD: HEMLOCK OR FIR
  - SIZES: 2" x 6" 1<sup>ST</sup> FLOOR EXTERIOR WALLS
  - 2" x 6" 2<sup>ND</sup> FLOOR EXTERIOR WALLS
  - 2" x 4" INTERIOR PARTITIONS
  
10. ROOF SHEATHING:
  - SIZE: 1/2" PLYWOOD
  
11. SHINGLES:
  - UNDERLAYMENT - #15 FELT PAPER; "LIFETIME" DIMENSIONAL SHINGLES BY GAF
  
12. GUTTERS (5K) AND DOWNSPOUTS:
  - MATERIAL: ALUMINUM

Initial \_\_\_\_\_

Initial \_\_\_\_\_

2

## PLYMOUTH VALLEY ESTATES SPECIFICATIONS (Lots 1-35)

13. FLASHING:

MATERIAL: ALUMINUM

14. WALL FINISHING:

(1) COAT OF PAINT ON ALL INTERIOR WALLS AND CEILINGS (COLOR: BONE), (1) COAT OF PRIMER AND (1) COAT OF GLOSS PAINT ON WOODWORK (COLOR: BONE). (IN SOME CASES, THE PRIMER COAT MAY BE APPLIED IN THE FACTORY)

15. INTERIOR DOORS AND TRIM:

TRIM: 3 ¼" COLONIAL CASING, 5 ¼" BASEBOARD.

CROWN MOLDING: 1 PIECE CROWN MOLDING IN LIVING ROOM (STUDY IF THERE IS NO LIVING ROOM), DINING ROOM, FAMILY ROOM AND POWDER ROOM

CHAIR RAIL: (1) PIECE IN DINING ROOM.

OG PICTURE MOLDING: DINING ROOM UNDER CHAIR RAIL

DOORS: 6'8" HIGH 6 PANEL MASONITE HOLLOW CORE ON FIRST AND SECOND FLOOR. - PAINT GRADE.

DOOR HARDWARE: KWIKSET (*Polo Style – SatinNickel finish*)

16. SASH AND EXTERIOR DOORS:

WINDOWS: VIWINCO SIGNATURE SERIES VINYL (DOUBLE HUNG)- INCLUDES ½ SCREENS. GRILLES INCLUDED ON FRONT, SIDES AND REAR (A FULL SCREEN(S) MAY BE NECESSARY AT THE SELLER'S DISCRETION) – COLOR - WHITE

DOORS: (FRONT) - 6 PANEL SMOOTH FIBERGLASS DOOR AS PER PLAN PAINTED  
(REAR) – VIWINCO SIGNATURE SERIES VINYL SLIDER – INCLUDES SCREEN AS PER PLAN.

17. CABINETS:

GATEHOUSE CABINETS BY CENTURY KITCHENS  
SELECTIONS TO BE MADE AT CENTURY KITCHENS  
(*42" High Kitchen Wall Cabinets with Crown Molding and Light Rail*)

18. COUNTERTOPS

- KITCHEN – CHOOSE FROM BUILDERS STANDARD SELECTION OF NATURAL STONE
- MASTER BATH – CHOOSE FROM BUILDERS STANDARD SELECTION OF NATURAL STONE
- HALL BATH OR PRIVATE BATH – CULTURED MARBLE- SELECTIONS TO BE MADE AT CENTURY KITCHENS

19. APPLIANCES

- GE (GAS OR ELECTRIC)
- 30" RANGE – STAINLESS STEEL FINISH
- MICROWAVE – STAINLESS STEEL FINISH
- DISHWASHER – STAINLESS STEEL FINISH
- REFRIGERATOR, WASHER AND DRYER NOT INCLUDED

## PLYMOUTH VALLEY ESTATES SPECIFICATIONS (Lots 1-35)

### 20. BATHROOMS AND ACCESSORIES:

**MASTERBATH:** SOAKER TUB (WHITE OR BISCUIT COLOR)  
FIBERGLASS SHOWERPAN BASE OR TILE BASE  
*(Subject to product availability based on shower base size)*  
STERLING WINDHAM by KOHLER ELONGATED  
TOILET- (WHITE OR BISCUIT COLOR)  
SINK- KOHLER CAXTON OVAL UNDERMOUNT SINKS  
*(Choice of White or Biscuit)*  
FLAT MIRROR ON WALL ABOVE VANITY  
MOEN BELFIELD CHROME SHOWER HEAD,  
TUB SPOUT AND FAUCETS  
FRAMED SHOWER DOOR WITH CHROME TRIM

**HALL BATH / PRIVATE BATH (S):** BOOTZ STYLE TUB OR  
FIBERGLASS SHOWER BASE AS PER PLAN  
STERLING WINDHAM by KOHLER ELONGATED  
FRONT TOILET- (WHITE OR BISCUIT COLOR)  
FLAT MIRROR ON WALL ABOVE VANITY  
MOEN CHATEAU CHROME *(Lever Style)* SHOWER AND  
TUB SPOUT  
MOEN CHATEAU CHROME *(Lever Style)* FAUCETS  
CHROME SHOWER CURTAIN ROD

**POWDER ROOM:** STERLING SACRAMENTO by KOHLER PEDESTAL  
SINK - (WHITE OR BISCUIT COLOR)  
STERLING WINDHAM by KOHLER ELONGATED  
FRONT TOILET- (WHITE OR BISCUIT COLOR)  
OVAL MIRROR ON WALL ABOVE SINK  
MOEN CHATEAU CROME *(Lever Style)* FAUCET

*TOILET PAPER HOLDERS AND TOWEL BARS NOT INCLUDED*

**KITCHEN:** MOEN CAMERIST CHROME FAUCET

### 21. STAIRS:

**BASEMENT:** YELLOW PINE WITH PINE HAND RAIL-UNFINISHED  
**MAIN:** OAK TREADS STAINED AND PINE RISERS PAINTED,  
OAK HANDRAIL STAINED AND POPLAR PAINTED  
SPINDLES ON MAIN LEVEL – ALL OVERLOOKS FROM  
SECOND LEVEL ARE ½ WALLS W/ PAINTED WOOD CAP  
**REAR:** YELLOW PINE CARPETED WITH OAK HANDRAIL  
STAINED AND POPLAR PAINTED SPINDLES.

## PLYMOUTH VALLEY ESTATES SPECIFICATIONS (Lots 1-35)

### 22. CERAMIC TILE (BATHROOMS):

**HALL BATHS / PRIVATE BATH (S):** 6" x 6" CERAMIC TILE, MATTE ON FLOORS, COORDINATING BASEBOARD AND GLOSS ON TUB WALLS TO 6' HEIGHT (*Choice of Colors*)

**MASTER BATH:** BRIXTON (CHOICE OF COLORS), HEATHLAND (WHITE ROCK) OR SKYBRIDGE - 12" x 12" CERAMIC TILE ON FLOORS, COORDINATING BASEBOARD AND 9" x 12" CERAMIC TILE ON TUB DECK AND SHOWER WALLS TO 6' HEIGHT (*Note: Skybridge Tile is 12" x 12" Floor and 10" x 14" Tub & Shower*)

**LAUNDRY ROOM** – 12"x12" BRIXTON, HEATHLAND OR SKYBRIDGE (CHOICE OF COLORS) (*5 1/4" Baseboard*)

**MUD ROOM** – BRIXTON OR SKYBRIDGE (CHOICE OF COLORS) 12" x 12" CERAMIC TILE (*5 1/4" Baseboard*)

### 23. HEATING:

1 ZONE (95%) OR 2 ZONE GAS HEAT WITH CENTRAL AIR SYSTEM ENGINEERED BY YORK. IF APPLICABLE, THE SECOND ZONE MAY BE BUILT AS A HONEYWELL ZONE DAMPER SYSTEM OR AN ADDITIONAL 80% SYSTEM INSTALLED IN THE ATTIC, AND IS SUBJECT TO CHANGE BASED ON HOUSE STYLE AND TOWNSHIP CODES. ONE PROGRAMMABLE THERMOSTAT IS INCLUDED ON THE FIRST FLOOR

### 25. ELECTRICAL WORK:

STANDARD BUILDERS LIGHTING PACKAGE  
200 AMP SERVICE  
SWITCHES AND RECEPTACLES BY TOWNSHIP CODE  
CIRCUIT BREAKERS  
ELECTRIC DRYER OUTLET (DRYER & CONNECTION BY BUYER)  
(6) RECESSED LIGHTS IN KITCHEN  
(2) ETHERNET CAT5e TELEPHONE JACKS  
\*\*\*ANY ADDITIONAL ELECTRICAL OUTLETS OR LINES MUST BE DISCUSSED WITH ELECTRICIAN AT THE SITE.

### 26. SECURITY SYSTEM

BASIC SECURITY SYSTEM: INCLUDES (1) BASEMENT MOTION DETECTOR, 1<sup>ST</sup> FLOOR DOORS, (1) MOTION DETECTOR, & (1) KEYPAD.  
\*\*\*ANY ADDITIONAL SECURITY FEATURES MUST BE DISCUSSED WITH THE SECURITY CONTRACTOR.

## **PLYMOUTH VALLEY ESTATES SPECIFICATIONS (Lots 1-35)**

### **27. HOME AUTOMATION – THE “GET SMART HOME PACKAGE” BY WORLD WIDE STEREO & VIDEO**

- 3 – TV PREMIUM WIRING INFRASTRUCTURE (1 COAXIAL CABLE-RG6 and 4 CAT6. ONE (1) TO BE CENTRALLY LOCATED FOR FUTURE REUTER)
- 2 - WIRING FOR FUTURE WIRELESS ACCESS POINTS (DUAL CAT 6)
- 2 – (ROOMS) WIRING FOR OPTIONAL FUTURE SPEAKERS ON THE 1<sup>st</sup> FLOOR – WIRING FOR FOUR (4) SPEAKERS TOTAL

ELECTRICIAN WILL INSTALL WIRING AS PER DIRECTION FROM WORLD WIDE STEREO FOLLOWING DESIGN MEETINGS WITH BUYER. IN THE EVENT BUYER CHOOSES TO UPGRADE FROM THE GET SMART HOME PACKAGE, WORLD WIDE STEREO MAY INSTALL ROUGH WIRING. UPGRADED HOME AUTOMATION MAY RESULT IN ADDITIONAL COSTS FOR THE BUYER.

### **28. INSULATION:**

MATERIAL: (FIBERGLASS) 6 ¼” BATT INSULATION (R-19) IN EXTERIOR WALLS, FOAM AND CAULK PACKAGE AT EXTERIOR PROTRUSIONS, BLOWN-IN INSULATION (R-30) IN ATTIC, R-11 FSK INSULATION AS REQUIRED BY CODE ON OF FOUNDATION WALLS IN BASEMENT, SOUND INSULATE BATHROOM AND LAUNDRY ROOM WALLS (WHERE POSSIBLE). INSULATED GARAGE WITH R-19 IN WALLS AND R-30 IN CEILING OR WALLS WHEN COMMON WITH LIVING SPACE. MATERIALS SUBJECT TO CHANGE BASED ON CODE REGULATIONS AT BUILDER’S DISCRETION.

### **29. GARAGE:**

TWO CAR FRONT ENTRY SINGLE 16 FT. WIDE GARAGE DOOR STANDARD.  
CLOPAY GARAGE DOOR–COACHMAN 4 PANEL INSULATED DOOR W/ SQ24 GLASS WINDOW PANES W/ GARAGE DOOR OPENER & KEYPAD

**PLYMOUTH VALLEY ESTATES SPECIFICATIONS (Lots 1-35)**

**30. PLUMBING:**

ALL SUPPLY TUBING AND PVC DRAIN LINES TO MEET TOWNSHIP CODE  
KITCHEN SINK (9" DEEP BLANCO UNDERMOUNT STAINLESS STEEL)  
BADGER ONE GARBAGE DISPOSAL 1/3 H.P.  
FROSTFREE FAUCETS WILL BE PROVIDED AT LOCATIONS TO BE DETERMINED BY THE JOB SUPERINTENDENT.  
SEWAGE PIPE AND WATER PIPE WILL BE INSTALLED IN ACCORDANCE WITH TOWNSHIP SUMP PUMP  
HOT WATER HEATER IS A 50 GALLON GAS HIGH EFFICIENCY  
LAUNDRY/UTILITY TUB IS EXCLUDED  
ICE MAKER LINE IS INCLUDED (CONNECTION TO BE PROVIDED BY BUYER)

**31. GRADING & LANDSCAPING:**

LANDSCAPING PACKAGE AND SITE TREES PER TOWNSHIP APPROVED PLAN. TREES AND SHRUBS SUBJECT TO CHANGE BASED ON AVAILABILITY. NO GUARANTEE FOR PLANTINGS.  
DISTURBED AREAS OF LOTS WILL BE RAKED AND SEEDED ONE TIME ONLY. IF WORK CANNOT BE DONE IN ANY WOODED AREAS OR AMONG TREES IN WHICH EQUIPMENT CAN'T OPERATE, THE AREA WILL BE LEFT NATURAL. BUILDER WILL NOT BE RESPONSIBLE FOR DRY WEATHER OR RAINS THAT HINDER THE GROWTH OF THE LAWN, SHRUBS AND TREES. HAULING IN OR OUT OF SOIL OR FILL IS NOT INCLUDED IN THIS CONTRACT. FINAL GRADING, SEEDING AND LANDSCAPING MAY BE COMPLETED AT A LATER DATE FOR HOMES THAT ARE

SETTLING BETWEEN NOVEMBER 15<sup>TH</sup> AND APRIL 15<sup>TH</sup>. THESE HOMES WILL BE COMPLETED AFTER MAY 15<sup>TH</sup> OR AS SOON AS WEATHER PERMITS.

**32. CLOSET SHELVING: VENTILATED VINYL**

**33. DRIVEWAY:**

BLACKTOP WILL BE INSTALLED FROM CURB DEPRESSION TO GARAGE DOOR. UP TO (100) SQUARE YARDS ALLOWANCE - 2 CAR GARAGE

**34. RADON:**

PREPARATORY PRECAUTIONS WILL BE TAKEN AGAINST POSSIBLE RADON PENETRATION WHEN CONSTRUCTING THE HOUSE.  
VENTILATION PIPE INSTALLED FROM UNDER THE BASEMENT SLAB, THRU THE HOUSE AND THRU THE ROOF.

Initial \_\_\_\_\_

Initial \_\_\_\_\_

7

## **PLYMOUTH VALLEY ESTATES SPECIFICATIONS (Lots 1-35)**

35. A 10% UP FRONT PAYMENT IS REQUIRED FOR ALL OPTIONS CHOSEN BY THE BUYER UPON APPROVAL OF THE SELECTION
36. IF THE NECESSARY PREPARATORY WORK IS NOT PART OF THE AGREEMENT OF SALE, BUILDER TAKES NO RESPONSIBILITY FOR FUTURE WORK BUYER MAY WANT TO DO IN REGARDS TO A FINISHED BASEMENT. BUYER MUST SPECIFY THAT THERE ARE PLANS FOR A FINISHED BASEMENT DURING THE DESIGN PROCESS IN WRITING.

### **DISCLOSURES**

BUILDER RESERVES THE RIGHT TO AN ESCALATION OF THE BASE SALE PRICE SHOULD ADDITIONAL DEVELOPMENT AND CONSTRUCTION EXPENSES BE INCCURED, PRIOR TO AND DURING CONSTRUCTION OF CUSTOM HOME. IN THE EVENT THE ESCALATION IS DEEMED NECESSARY, BUYER WILL BE NOTIFIED IN WRITING OF SAID ESCALATION, AND WILL HAVE SEVEN (7) DAYS TO ACCEPT THE INCREASE. SHOULD THE INCREASE NOT BE ACCEPTED, BUYER MAY DECLARE THE AGREEMENT OF SALE NULL AND VOID, AT WHICH TIME DEPOSIT MONIES WILL BE RETURNED WITH NO LIABILITY TO EITHER PARTY.

IN SOME MODELS, CROWN MOLDING, CHAIR RAIL AND HARDWOOD FLOORING LOCATIONS MAY BE INSTALLED IN A DIFFERENT LOCATION OR MAY NOT BE INCLUDED DUE TO THE DESIGN OF THE HOUSE. SEE BUILDER FOR CLARIFICATION.

WHEN SLOPED CEILINGS OR WHEN NO CLEAR ROOM BREAK LOCATION CAN BE ESTABLISHED – SEE BUILDERS REPRESENTATIVE FOR SPECIFIC DETAILS

MATERIALS INCLUDING BUT NOT LIMITED TO HARDWOOD FLOORS, INTERIOR TRIM, CONCRETE AND NATURAL STONES INCLUDING BUT NOT LIMITED TO COUNTERTOPS, TILE, FIREPLACE SURROUNDS AND REAL OR MANUFACTURED EXTERIOR STONE WILL HAVE COLOR AND TEXTURE VARIATIONS. ANY IRREGULAR ASPECT IS THE GUARANTEE OF THE PRODUCTS NATURAL AND AUTHENTIC SOURCE. THIS IS NOT AND SHALL NOT BE CONSIDERED A PRODUCT DEFECT.



SETTLEMENT DATE STATED IN AGREEMENT OF SALE IS ESTIMATED. BUILDER WILL MAKE EVERY EFFORT TO ACHIEVE THIS DATE, HOWEVER THERE IS ABSOLUTELY NO GUARANTEE. A FINAL SETTLEMENT DATE WILL BE GIVEN AT THE COMPLETION OF INTERIOR TRIM ASSUMING ALL SELECTIONS HAVE BEEN MADE BY THE BUYER AND ALL PAYMENTS FOR OPTIONS HAVE BEEN RECEIVED BY THE BUILDER.

\_\_\_\_\_  
**BUYER**

\_\_\_\_\_  
**DATE**

\_\_\_\_\_  
**BUYER**

\_\_\_\_\_  
**DATE**